

# Bid Results

## Bidder Details

Vendor Name	SNZ Contractors Inc.
Address	8583 Irvine center Dr #224
	Irvine, California 92618
	United States
Respondee	SNZ Contractors
Respondee Title	CEO
Phone	949-649-4119
Email	projects@snzconinc.com
Vendor Type	OSB
License #	1097225
	CADIR

## Bid Detail

Bid Format	Electronic
Submitted	07/06/2023 11:17 AM (PDT)
Delivery Method	
Bid Responsive	
Bid Status	Submitted
Confirmation #	337323

## Respondee Comment

## Buyer Comment

## Attachments

File Title	File Name	File Type
Bid Documents.pdf	Bid Documents.pdf	Proposal Documents
Signed Bid Bond.pdf	Signed Bid Bond.pdf	Bid Bond

Subcontractors

No Subcontractors

Line Items

Discount Terms    No Discount

Item #	Item Code	Type	Item Description	UOM	QTY	Unit Price	Line Total	Response	Comment
GENERAL							\$15,500.00		
1			MOBILIZATION/DEMOBILIZATION	LS	1	\$5,000.00	\$5,000.00	Yes	
2			CLEARING, GRUBBING, AND MISCELLANEOUS REMOVALS	LS	1	\$8,000.00	\$8,000.00	Yes	
3			BEST MANAGEMENT PRACTICE WPCP AND NPDES REQUIREMENTS PER BID DOCUMENT	LS	1	\$2,500.00	\$2,500.00	Yes	
CIVIL-STREET							\$99,595.00		
4			REMOVE EXISTING PCC SIDEWALK AND CURB RAMP	SF	120	\$5.00	\$600.00	Yes	
5			CONSTRUCT 4" PCC SIDEWALK OVER 12" MINIMUM 90% COMPACTED NATIVE SUBGRADE PER CITY OF FONTANA STD. PLAN NO. 1006.	SF	1250	\$15.00	\$18,750.00	Yes	
6			REMOVE EXISTING AND CONSTRUCT 4" A.C. DRIVEWAY TRANSITION OVER 12" MINIMUM 95% COMPACTED NATIVE SUBGRADE.	SF	160	\$30.00	\$4,800.00	Yes	
7			REMOVE EXISTING AND CONSTRUCT NEW 6" PCC DRIVEWAY TRANSITION OVER 12" MINIMUM 95% COMPACTED NATIVE SUBGRADE.	SF	700	\$25.00	\$17,500.00	Yes	
8			CONSTRUCT 6" PCC RESIDENTIAL DRIVEWAY RAMP OVER 12" MINIMUM 95% COMPACTED NATIVE SUBGRADE PER CITY OF FONTANA STD. PLAN NO. 1001	SF	450	\$30.00	\$13,500.00	Yes	
9			CONSTRUCT 6.5" A.C. PAVEMENT OVER 4' OF 12" MINIMUM 95% COMPACTED NATIVE SUBGRADE PER CITY OF FONTANA STD. PLAN NO. 1008.	TON	20	\$275.00	\$5,500.00	Yes	
10			REMOVE BLOCK WALL AND MAKE REPAIRS TO MATCH EXISTING FACING.	LF	6	\$500.00	\$3,000.00	Yes	
11			CONSTRUCT 8" CURB INTEGRAL WITH SPANDREL. MATCH EXISTING CURB WITH NEW CURB RAMP.	LF	35	\$2.00	\$70.00	Yes	
12			REMOVE EXISTING SPANDREL AND CONSTRUCT 8" PCC SPANDREL OVER 12" MINIMUM COMPACTED NATIVE GRADE	SF	180	\$30.00	\$5,400.00	Yes	
13			CONSTRUCT CURB RAMP OVER 12" MINIMUM 95% COMPACTED NATIVE SUBGRADE PER CITY OF FONTANA STD. NO. 1003.	EA	1	\$7,500.00	\$7,500.00	Yes	
14			REMOVE AND REPLACE EXISTING 8" CURB AND GUTTER OVER 12" MINIMUM 95% COMPACTED NATIVE SUBGRADE PER CITY OF FONTANA STD. PLAN NO. 1000.	LF	90	\$25.00	\$2,250.00	Yes	
15			REMOVE/MODIFY EXISTING HARDSCAPE/LANDSCAPE AND IRRIGATION AS NEEDED (MATCH EXISTING)	LS	1	\$5,000.00	\$5,000.00	Yes	
16			CONSTRUCT 2" A.C. OVERLAY.	TON	23	\$275.00	\$6,325.00	Yes	
17			GRIND EXISTING A.C. PAVEMENT 2" MINIMUM.	SF	1600	\$4.00	\$6,400.00	Yes	
18			ADJUST EXISTING WATER METER AND PULLBOX TO GRADE.	EA	4	\$500.00	\$2,000.00	Yes	
19			REMOVE AND REPLACE EXISTING MAILBOX AND POST.	EA	2	\$500.00	\$1,000.00	Yes	

Line Item Subtotals

Section Title	Line Total
GENERAL	\$15,500.00
CIVIL-STREET	\$99,595.00
Grand Total	\$115,095.00