

Bid Results

Bidder Details

Vendor Name	CT&T Concrete Paving Inc.
Address	324 S. Diamond Bar Blvd. Diamond Bar, California 91765 United States
Respondee	Jose Carvajal
Respondee Title	President
Phone	909-629-8000
Email	jose.cttinc@gmail.com
Vendor Type	CADIR, OSB
License #	875627
CADIR	1000025154

Bid Detail

Bid Format	Electronic
Submitted	08/03/2023 1:52 PM (PDT)
Delivery Method	
Bid Responsive	
Bid Status	Submitted
Confirmation #	340608

Respondee Comment

Buyer Comment

Attachments

File Title	File Name	File Type
Fontana SRTS Proposal Documents - CTT.pdf	Fontana SRTS Proposal Documents - CTT.pdf	Proposal Documents
Fontana SRTS Bid Bond - CTT.pdf	Fontana SRTS Bid Bond - CTT.pdf	Bid Bond

Subcontractors

Showing 5 Subcontractors

Name & Address	Desc	License Num	CADIR	Amount	Type
California Professional Engineering, 19062 San Jose Ave La Puente, California 91748	Items 39-41, 43	793907	1000377609	\$159,235.00	DBE, OSB
Chrisp Company 2280 S. Lilac Ave. Bloomington, California 92316	Signage & Striping	374600	1000000306	\$267,515.00	CADIR
Elecnor Belco Electric, Inc. 14320 Albers Way Chino, California 91710	Item 44 - Relocate existing vault, fiber conduit, and cables as needed and directed	738518	1000004804	\$29,000.00	
Granstrom Masonry, Inc. 19530 Normandie Ave Torrance, California 90504	Masonry	629489	1000004794	\$70,722.00	
treesmith enterprises 1551 n miller street anaheim, California 92806	Tree Removals	802705	1000001838	\$47,850.00	OSB, WBE, MBE

Line Items

Discount Terms No Discount

Item #	Item Code	Type	Item Description	UOM	QTY	Unit Price	Line Total	Response	Comment
Section name required							\$3,615,087.50		
1			Mobilization/ Demobilization (including During Utility Window)	LS	1	\$416,000.00	\$416,000.00	Yes	
2			Clearing, Grubbing, and Miscellaneous Removals	LS	1	\$75,000.00	\$75,000.00	Yes	
3			Temporary Traffic Control (including During Utility Window)	LS	1	\$45,000.00	\$45,000.00	Yes	
4			Water Pollution Control Best Management Practices	LS	1	\$10,000.00	\$10,000.00	Yes	
5			Remove and Dispose Existing Trees, Stump, and Roots to 3ft Below Finish Surface	EA	66	\$833.75	\$55,027.50	Yes	
6			Remove Existing and Construct 8" Cross Gutter/Spandrel Over 12" Min. of 95% Compacted Native per City of Fontana Standard Plan No. 403.	SF	5009	\$14.00	\$70,126.00	Yes	
7			Remove Existing and Construct 6" Curb Over 12" Min. of 95% Compacted Native per City of Fontana Standard Plan No. 1000.	LF	11	\$80.00	\$880.00	Yes	
8			Remove Existing and Construct 6" Curb and Gutter Over 12" Min. of 95% Compacted Native per City of Fontana Standard Plan No. 1000.	LF	671	\$60.00	\$40,260.00	Yes	
9			Remove Existing And Construct 8" PCC Residential Driveway Over 12" Min. of 95% Compacted Native per City of Fontana Standard Plan No. 1001. Type As Shown Per Plan.	SF	18931	\$14.25	\$269,766.75	Yes	
10			Remove Existing And Construct Retaining Curb Over 12" Min. of 95% Compacted Native As Shown On Plans.	LF	308	\$62.00	\$19,096.00	Yes	
11			Remove Existing And Construct Curb Ramp Per City Of Fontana Standard Plan No. 1003 Over 12" Min of 95% Compacted Native. Type as Shown per Plan.	EA	21	\$7,250.00	\$152,250.00	Yes	
12			Remove Water Fountain Including Electrical.	LS	1	\$4,000.00	\$4,000.00	Yes	
13			Remove Existing And Construct 4" PCC Sidewalk Over 12" Min. over 95% Compacted Native per City of Fontana Standard Plan No. 1006.	SF	48195	\$11.00	\$530,145.00	Yes	
14			Remove Existing And Construct Curb Ramp Per SPPWC Plan No. 111-5 Over 12" Min. over 95% Compacted Native. Case And Type As Shown Per Plan.	EA	11	\$7,250.00	\$79,750.00	Yes	
15			Remove Existing AC Pavement (12" Deep), Construct 12" Thick Full Depth AC Pavement Over 90% Compacted Native, Minimum 4' Wide.	TON	1452	\$275.00	\$399,300.00	Yes	
16			Remove Existing and Construct 6.5" Min. AC Pavement Over 12" Min. over 95% Compacted Native Subgrade Per City Std. 401.	TON	213	\$250.00	\$53,250.00	Yes	
17			Remove Existing and Construct 4" AC Pavement Over 95% Compacted Native at the Back of Driveway.	TON	102	\$240.00	\$24,480.00	Yes	
18			Remove Existing and Construct 4" PCC Over 95% Compacted Native at The Back of Driveway.	SF	16350	\$13.00	\$212,550.00	Yes	
19			Grind Existing Pavement With 0.20' AC Min.	SF	3300	\$5.00	\$16,500.00	Yes	
20			Overlay Existing Pavement With 0.20' AC Min.	TON	61	\$200.00	\$12,200.00	Yes	
21			Relocate Chain Link Fence Per SPPWC Standard Plan No. 600-4.	LF	1163	\$46.00	\$53,498.00	Yes	
22			Remove and Reinstall Rolling Gate and Track.	EA	43	\$1,092.50	\$46,977.50	Yes	
23			Relocate Existing Fence and Driveway Gate	EA	58	\$1,380.00	\$80,040.00	Yes	
24			Remove Existing and Construct Wall Per SPPWC Standard Plan No. 621-3. Material, Finish, Height and Color Shall Match Existing and as Shown On Plans. Relocate Wrought Iron Fence on Top of the Wall.	LF	121	\$550.00	\$66,550.00	Yes	
25			Adjust Water Cover to Grade.	EA	117	\$250.00	\$29,250.00	Yes	
26			Adjust Fire Hydrant to Grade.	EA	2	\$3,500.00	\$7,000.00	Yes	
27			Adjust Utility Cover to Grade.	EA	2	\$2,500.00	\$5,000.00	Yes	
28			Remove Existing and Reinstall Mailbox as Shown on Plans.	EA	120	\$450.00	\$54,000.00	Yes	
29			Remove Existing and Construct Mailbox as Shown on Plans.	EA	4	\$1,000.00	\$4,000.00	Yes	
30			Remove Existing and Relocate Wrought Iron Fence as Shown on Plans.	LF	319	\$74.75	\$23,845.25	Yes	
31			Remove Existing and Install New Chain Link Fence per SPPWC Standard Plan No. 600-4.	LF	573	\$69.00	\$39,537.00	Yes	
32			Remove Existing and Construct Wall per SPPWC Standard Plan No. 601-5. Material, Finish, Height and Color Shall Match Existing and as Shown on Plans.	LF	100	\$475.00	\$47,500.00	Yes	
33			Relocate Utility Box, Meter, and Irrigation Valve	EA	12	\$1,250.00	\$15,000.00	Yes	
34			Restore Landscaping and Irrigation in Kind	LS	1	\$65,000.00	\$65,000.00	Yes	
35			Remove All Existing Conditions and Construct 8" Curb Over 12" Min. of 95% Compacted Native per City of Fontana Standard Plan No. 1000.	LF	330	\$75.00	\$24,750.00	Yes	
36			Remove All Existing Conditions and Construct 8" Curb and Gutter Over 12" Min. of 95% Compacted Native per City of Fontana Standard Plan No. 1000.	LF	305	\$78.00	\$23,790.00	Yes	
37			Remove All Existing Conditions and Construct Cobble Rock in Kind.	SF	22	\$98.00	\$2,156.00	Yes	
38			Install Utility Box and Cover (Allowance)	EA	100	\$175.00	\$17,500.00	Yes	
39			Traffic Signal - RRFB Including Electrical (Oleander Ave and Sequoia Ave) per Street Lighting Plans and Southern California Edison Drawing No. 1624548_0.01	LS	1	\$43,700.00	\$43,700.00	Yes	
40			Traffic Signal - RRFB Including Electrical (Mallory Dr and Skyland Ct) per Street Lighting Plans and Southern California Edison Drawing NO. 1624757_0.01	LS	1	\$43,700.00	\$43,700.00	Yes	
41			Street Lighting Installation per Construction Street Lighting Plans and Southern California Edison Drawing No. 1625045_01.01	LS	1	\$70,725.00	\$70,725.00	Yes	
42			Signing and Striping as shown on the Plans	LS	1	\$307,642.25	\$307,642.25	Yes	
43			Install Traffic Signal Loops per Caltrans Standard Plans and Traffic Signal Detection Plans	EA	63	\$396.75	\$24,995.25	Yes	
44			Relocate Existing Vault. Relocate All Existing Fiber Conduit and Cables as Needed and as Directed By the Engineer.	LS	1	\$33,350.00	\$33,350.00	Yes	

Line Item Subtotals

Section Title	Line Total
Section name required	\$3,615,087.50
Grand Total	\$3,615,087.50