

Bid Result

Bidder Details

Vendor Name Kalban, Inc.
Address 26450 Ruether Ave Unit 201
Santa Clarita, California 91350
United States
Respondee Matt Lawrence
Respondee Title Vice President
Phone 818-612-0388
Email mattlawrence061891@gmail.com
Vendor Type OSB
License # 507550
CADIR

Bid Detail

Bid Format Electronic
Submitted 04/02/2026 12:57 PM (PDT)
Delivery Method
Bid Responsive
Bid Status Submitted
Confirmation # 478244

Respondee Comment

Buyer Comment

Attachments

File Title	File Name	File Type
Kalban Proposal Fontana.pdf	Kalban Proposal Fontana.pdf	Proposal Documents to Upload
doc20260402125040.pdf	doc20260402125040.pdf	Bid Bond

Subcontractors

Showing 3 Subcontractors

Name & Address	Desc	License Num	CADIR	Amount	Type
ONYX PAVING COMPANY INC. 22707 LA PALMA AVE. YORBA LINDA, California 92887	Grind and Overlay	630360	1000004798	\$62,000.00	
Superior Pavement Markings 5312 Cypress Street Cypress, California 90630	Striping	1141887	2000015240	\$5,300.00	
treemith enterprises 1551 n miller street anaheim, California 92806	Tree Removal	802705	1000001838	\$10,500.00	OSB, WBE, MBE

Line Items

Discount Terms No Discount

Item #	Item Code	Type	Item Description	UOM	QTY	Unit Price	Line Total	Response	Comment
GENERAL							\$32,000.00		
1	1		Mobilization/Demobilization	LS	1	\$10,000.00	\$10,000.00	Yes	
2	2		Clearing and Grubbing; Miscellaneous Removals	LS	1	\$10,000.00	\$10,000.00	Yes	
3	3		WPCP, BMP, and NPDES Requirements Per Bid Documents	LS	1	\$10,000.00	\$10,000.00	Yes	
4	4		Project Notifications	LS	1	\$2,000.00	\$2,000.00	Yes	
CIVIL - STREET							\$734,971.00		
5	5		Remove and Replace/Reconstruct Landscape or Hardscape and Irrigation in Kind, To Like Condition or Better, As Required for Improvements	LS	1	\$10,000.00	\$10,000.00	Yes	
6	6		Remove and Replace/Relocate Existing Chain Link Fence Per SPPWC Std 600-3	LS	1	\$5,000.00	\$5,000.00	Yes	
7	7		Remove and Replace/Relocate Existing Chain Link Gate, Including Gate And/Or Gate Rail as Needed	LS	1	\$5,000.00	\$5,000.00	Yes	
8	8		Remove and Replace/Relocate Existing Wrought Iron Gate, Including Gate And/Or Gate Rail as Needed	LS	1	\$5,000.00	\$5,000.00	Yes	
9	9		Remove/Relocate and Install ADA Compliant Mailbox and Post Behind Curb Per USPS Standard	EA	31	\$700.00	\$21,700.00	Yes	
10	10		Remove Existing PCC Sidewalk, Walkway, Driveway Approach/Transition, and/or Curb Ramp	SF	11760	\$3.00	\$35,280.00	Yes	
11	11		Sawcut and Remove Existing AC Pavement	SF	4540	\$3.00	\$13,620.00	Yes	
12	12		Remove Existing and Construct 6" PCC Curb and Gutter Per City of Fontana Std 1000 As Shown on Plans	LF	850	\$100.00	\$85,000.00	Yes	
13	13		Grind 0.17' Min AC Pavement Per City of Fontana Std 1008	SF	15210	\$1.10	\$16,731.00	Yes	
14	14		Overlay 0.17' Min AC Pavement Per City of Fontana Std 1008	TON	255	\$170.00	\$43,350.00	Yes	
15	15		Remove Existing Tree and Roots	EA	10	\$1,200.00	\$12,000.00	Yes	
16	16		Remove and Replace Decorative Pavers, In Kind, As Needed for Improvements	LS	1	\$5,000.00	\$5,000.00	Yes	
17	17		Construct 2.5" AC Pavement Over 12" Min. 95% Compacted Native Subgrade Per City of Fontana Std 1008	TON	85	\$350.00	\$29,750.00	Yes	
18	18		Construct 6" PCC Residential Driveway with Curb Adjacent Sidewalk Over 12" Min. 95% Native Compaction Per City of Fontana Std 1001	SF	3830	\$18.00	\$68,940.00	Yes	
19	19		Construct 6" PCC Driveway Transition Over 12" Min. 95% Native Compaction	SF	6050	\$18.00	\$108,900.00	Yes	
20	20		Construct PCC Curb Ramp Per City of Fontana Std 1003, Dwg 2	EA	2	\$7,000.00	\$14,000.00	Yes	
21	21		Construct PCC Curb Ramp Per City of Fontana Std 1003, Dwg 1	EA	1	\$7,000.00	\$7,000.00	Yes	
22	22		Construct 4" PCC Sidewalk, Width as Noted (Including Retaining Curb at Back of Walk as Required) Per City of Fontana Std Plan 1006	SF	9340	\$18.00	\$168,120.00	Yes	
23	23		Construct 6" PCC Modified Curb Ramp as Shown on Plans and Per City of Fontana Std 1003	EA	1	\$7,000.00	\$7,000.00	Yes	
24	24		Remove and Reconstruct 8" PCC Cross Gutter and/or Spandrel Per City of Fontana Std 1013	SF	1200	\$25.00	\$30,000.00	Yes	
25	25		Construct 6" PCC Stamped Concrete Driveway Transition, In Kind, over 12" Min 95% Native Compaction	SF	840	\$22.00	\$18,480.00	Yes	
26	26		Adjust Existing Manhole to Finish Grade	EA	5	\$1,500.00	\$7,500.00	Yes	
27	27		Adjust Existing Water Meter/Gas Valve to Finish Grade	EA	31	\$400.00	\$12,400.00	Yes	
28	28		Construct 4" PCC Sidewalk Per City of Fontana Std 1006	SF	250	\$18.00	\$4,500.00	Yes	
29	29		Furnish and Install Detectable Warning Surface (Truncated Dome), Per City of Fontana Std 1003	EA	1	\$700.00	\$700.00	Yes	
Civil-Traffic							\$16,500.00		
30	30		Temporary Traffic Control (Including Traffic Control Plans) Implemented and Maintained for Entire Project Duration	LS	1	\$10,000.00	\$10,000.00	Yes	
31	31		Signing, Striping and Pavement Markers (Whether Applying, Reapplying, or Refreshing) Complete	LS	1	\$6,500.00	\$6,500.00	Yes	

Line Item Subtotals

Section Title	Line Total
GENERAL	\$32,000.00
CIVIL - STREET	\$734,971.00
Civil-Traffic	\$16,500.00
Grand Total	\$783,471.00